

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970
 IOSCO COUNTY REMONUMENTATION

For corners IOSCO Located In: _____ Corner Code # _____

1. Public Land Survey T 23 R 9 E-5
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
 IOSCO COUNTY
 FILED

21 NOV 97 12:47 P.M.

DONITA M. COYLE
 REGISTER OF DEEDS

97-28

Register of Deeds Stamp & File Number

I, WILLIAM E. WOODS P.S., in a field survey on NOV.17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1843 ORIGINAL SURVEY SET WOOD POST
 J.F. MUNRO FIR 6" DIAM. BEARS N39°E 26 LINKS
 B. ASH 10" DIAM. BEARS S12°E14 LINKS

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 9-16-97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

James H. Krantz

R.L. MILLER SURVEY R.L. MILLER SURVEY OF SW 1/4 SECTION 9
 DATE UNKNOWN

 DATE UNKNOWN NELS SET 1/2 BAR, RE-ESTABLISHED
 CORNER FROM MILLER SURVEY.

C. Description of monument for corner and accessories established to perpetuate locating the position of the come
 FOUND 1/2 BAR NO CAP 33' WEST OF R.L.M ROW IRON REPLACED WITH
 5/8 ROD AND REMON CAP
 S 53° W 51.29' TO 12" MAPLE, SET NAIL AND TAG, SE SIDE
 S 35° E 62.70' TO 12" MAPLE, SET NAIL AND TAG, NE SIDE
 N 35° E 59.61' TO TRIPLE MAPLE, SET NAIL AND TAG, SE SIDE
 N 62° W 50.23' TO TRIPLE MAPLE, SET NAIL AND TAG, NE SIDE



Signed by William E. Woods Date 11-20-97
 WILLIAM E. WOODS P.S.
 Surveyor's Michigan License No. 25882

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

**SURVEY &
 REMONUMENTATION**

MAR 18 1998

SECTION