

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

IOSCO COUNTY REMONUMENTATION

For corners IOSCO Located In: _____ Corner Code # _____

1. Public Land Survey	T	<u>23</u>	R	<u>9</u>	E-6	
	T		R			
	T		R			
	T		R			
2. Property Controlling in Section	S		T		R	
	S		T		R	
3. Miscellaneous Property in Sec.	S		T		R	
	S		T		R	
4. Lot No. _____, Recorded Plat _____						
5. Private Claims _____						

STATE OF MICHIGAN
IOSCO COUNTY
FILED

21 NOV 97 12:46 P.M.

RONITA M. COYLE
REGISTER OF DEEDS

97-27

Register of Deeds Stamp & File Number

I, WILLIAM E. WOODS P.S., in a field survey on NOV 17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1843 ORIGINAL SURVEY J.F. MUNRO	SET WOOD POST CEDAR 12" DIAM. BEARING N 19° E, 20 LINKS BLACK ASH 6" DIAM. BEARING S 57° W, 17 LINKS
------------------------------------	--

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 9-16-97

James H. Stranger

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

APRIL 1996 L.C.R.C. R. L. MILLER	FOUND 2" WELL POINT RELIED ON AND RECONIZED AS 1/4 CORNER BY OTHER SURVEYORS S 15° E 10.4', 6" STEEL GATE POST, S 15° W, 21.55' TAG IN 10" ASH, N 69.20' TAG IN 10" ASH
1997 REMONUMENTATION WILLIAM E. WOODS	FOUND 2" WELL POINT CORNER OF RECORD. ALSO FOUND WITNESS 6" STEEL GATE POST, S 15° E, 10.41' TAG IN 10" ASH, N 60.20' TAG IN 10" ASH, S 15° W, 21.55' E 19.8' 6" GATE POST

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8 REBAR AND REMON CAP IN 3/4 PIPE 48" LONG WELL POINT GUARD PIPE

S 15° E 10.40' 6" STEEL GATE POST
S 15° W 21.55' WITNESS TAG R.L. MILLER 10" ASH
N 69.20' WITNESS TAG R.L. MILLER 10" ASH
S 88° E 19.75' 6" STEEL GATE POST



Signed by William E Woods Date 11-20-97
WILLIAM E. WOODS P.S.
Surveyor's Michigan License No. 25882

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

SURVEY &
REMONUMENTATION

MAR 18 1998

SECTION