

95-31

IOSCO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

IOSCO (County)	Located In:	Corner Code #
1. Public Land Survey	T 23 N 9 E	G-3
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
IOSCO COUNTY
FILED

12 DEC 95 2:29 P.M.

BONITA M. COBLE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, WILLIAM E. WOODS in a field survey on 1-2, 19 95 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1843 ORIGINAL SURVEY, JOHN MULLET SET POST

20" W PINE S 26°W
20" W PINE N 30°E

ACCEPTED BY THE IOSCO COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER P.A.
345 OF 1990 AT A MEETING
HELD ON 10-31-95

James H. Granger

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1889 SUBDIVISION, DANIEL E. GUILLEY MOWAT L. 2. P. 22
ADDITION TO CITY OF AUSABLE. CORNER IS NE CORNER OF SUBDIVISION.
1982 CORNER RECORDED, JAMES E. MURPHY FOUND 3/4" IRON BAR IN ASPHALT PAVEMENT AT INTERSECTION OF FOREST RD. & OLD US-23, NOTED AS "IRON PIPE" ON SURVEY PLAN BY OTIS D. LOVE, P.E., RLS APRIL, 19964
3/4" IRON BAR (N.W. CORNER SECTION)
N.E., 44.64' TAG NO. 528 IN UTILITY POLE
EAST, 15" EDGE OF ASPHALT PAVEMENT
S.W. 40.10" TAG NO. 513 IN UTILITY POLE
N.W. 41.18' TAG NO. 452 IN UTILITY POLE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
1995 REMONUMENTATION, WILLIAM E. WOODS
ACCEPT POSITION AS ESTABLISHED BY SUBDIVISION, FOUND PAVEMENT
SET 5/8 X 30 RE-ROD IN PAVEMENT BOX WITH ALUMINUM CAP
P.P N310°W 40.75
P.P S220°W 40.86
P.P S130°E 50.13
P.P N60°E 44.15



Signed by William E Woods
Surveyor's Michigan License No. 25882

Date 12-8-95