

75.2 & 7 1006

95-32

IOSCO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>IOSCO</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T 23 R 9 E</u>	<u>G-4</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

STATE OF MICHIGAN
IOSCO COUNTY
FILED

12 DEC 95 2:29 P.M.

RONITA H. COYLE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

WILLIAM E. WOODS in a field survey on 10-2-, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1843 ORIGINAL SURVEY, J.F. MUNRO SET POST

Y. PINE 12" N72°W 24LK
Y. PINE 10" S52°E 31LK


ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 10-31-95

James H. Granger

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1958 SUBDIVISION, CARL R. SMALL SUBDIVISION DESCRIPTION COMMENCES AT THIS CORNER. IT IS REFERRED TO AS NE CORNER GOVERNMENT LOT 2 SECTION 9.
1959 SUBDIVISION, R.J. COOKE POINT OF BEGINNING L.9 P. 11-12 FOR BRADY'S BIG PINES NO. 1 NE CORNER LOT 43 SHOWS CONCRETE MONUMENT.
FOUND CONCRETE MONUMENT

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
1995 REMONUMENTATION, WILLIAM E. WOODS ACCEPTED POSITION AS ESTABLISHED BY SUBDIVISION
PLACED RE-MON ALUMINUM CAP ON CONCRETE MONUMENT.

24" OAK S235°W 12.50
24" TRIPLE W. PINE S140°E 24.15
30" W. PINE S95°E 35.72
18" TWIN LOCUS N355°W 46.18



Signed by William E Woods
Surveyor's Michigan License No. 25882

Date 12-8-95