

SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

REMONUMENTATION CORNER LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
IOSCO COUNTY
FILED

5 DEC 94 2:00 P.M.

BONITA M. COYLE
REGISTER OF DEEDS

94-32

Register of Deeds Stamp & File Number

For corners in

_____ IOSCO _____ (County)	Located In:	Corner Code =#
1. Public Land Survey	T <u>23N</u> R <u>9E</u>	<u>G-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John F. Oliver in a field survey on September 13, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1844 Original Survey, William Johnston, Corner is Y. Pine 14" No witnesses

1944 Subdivision AuSable Point Beach No.2 (L.4 P. 32-35) Indicates corner point of beginning, being a concrete monument, by R.J. Cooke

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Accept position as established by subdivision.
found 4" X 4" Square concrete monument, set aluminum cap on monument


ACCEPTED BY THE IOSCO COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER P.A.
345 OF 1990 AT A MEETING
HELD ON 11-10-94

James H. [Signature]

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

4" X 4" Square concrete monument with aluminum cap

- 10" Red Oak North 51.55
- 22" Red Oak S65°E 22.00
- 18" Red Oak S44°W 26.46
- 18" Jack Pine N72°E 2.68



Signed by _____
Surveyor's Michigan License No. 19840

Date 11-11-94