

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970


FEB 15 2001

SECTION

For corners in IOSCO Located In: Corner Code #

- 1. Public Land Survey T 24N R 9E A-1
T 24N R 8E M-1
T 25N R 9E A-13 ALCONA
T 25N R 8E M-13 ALCONA
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S
4. Lot No. Recorded Plat

058 2000



Register of Deeds Stamp & File Number

5. Private Claims

I, WILLIAM E. WOODS P.S., in a field survey on OCT. 16, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. Cell (2,6) contains a black dot.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1843: ORIGINAL GOVERNMENT NOTES

SET POST
HEMLOCK 36" N64°W 23 LKS.
HEMLOCK 22" S62°E 23 LKS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: WILLIAM E. WOODS
2000: WILLIAM E. WOODS

FOUND PAVEMENT BOX AT CORNER LOCATION
FOUND PAVEMENT BOX WITH 1/2" REROD REPLACED WITH 5/8" REROD & REMON ALUMINUM CAP

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 10-11-2000

James H. Granger

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" REROD WITH REMON ALUMINUM CAP

P.P. S01°E 28.26' NAIL & TAG
NORWAY PINE 16" S42°W 48.28' NAIL & TAG
CEDAR POST (FENCE CORNER) 8" N28°W 55.94' NAIL & TAG
POPLAR 6" N40°E 52.26' NAIL & TAG



Signed by William E Woods

Date 12-06-2000

WILLIAM E. WOODS P.S.

Surveyor's Michigan License No. 25882