

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

IOSCO COUNTY REMONUMENTATION

For corners IOSCO Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

- |                                       |   |             |            |      |  |
|---------------------------------------|---|-------------|------------|------|--|
| 1. Public Land Survey                 |   | T <u>23</u> | R <u>9</u> | A-1  |  |
|                                       |   | T <u>24</u> | R <u>9</u> | A-13 |  |
|                                       |   | T <u>24</u> | R <u>8</u> | M-13 |  |
|                                       |   | T <u>23</u> | R <u>8</u> | M-1  |  |
| 2. Property Controlling in Section    | S | T           | R          |      |  |
|                                       | S | T           | R          |      |  |
| 3. Miscellaneous Property in Sec.     | S | T           | R          |      |  |
|                                       | S | T           | R          |      |  |
| 4. Lot No. _____, Recorded Plat _____ |   |             |            |      |  |
| 5. Private Claims _____               |   |             |            |      |  |

STATE OF MICHIGAN  
IOSCO COUNTY  
FILED

21 NOV 97 1:08 P.M.

RONITA M. COYLE  
REGISTER OF DEEDS

## 97-40

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, WILLIAM E. WOODS P.S., in a field survey on NOV. 17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- |                  |                                  |
|------------------|----------------------------------|
| 1837 SURVEY BY   | SET WOOD POST                    |
| LEWIS CLASON, DS | 18" Y. PINE S 83° W, 42 LINKS    |
|                  | 6" SPRUCE PINE N 65° S, 61 LINKS |

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 9-16-97

*James H. Strange*

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- |                         |   |
|-------------------------|---|
| 1908 W. G. FARGO SURVEY | FOUND 1 1/4" PIPE BELOW SURFACE, 2 RED CLAY BRICKS, IRON CUTTER SHOE.   |
| 1960 GEORGE BLASS       | 4" SQUARE ROTTED PINE STAKE, NO WITNESSES WERE TAKEN  |
|                         | PLACED 30 LB. SPIKE WITH WASHER IN CENTER LINE OF ROAD, CIRCULAR 6" X 5' LONG   |
|                         | REINFORCED CONCRETE REF. MONUMENT 18" ABOVE GROUND 33' DUE NORTH OF RECOVERED CORNER POINT. MONUMENT CAPPED BY 3 1/2" BRASS PLATE |
|                         | 10" JACK PINE N41°30' E, 69.83' SCRIBED BT 31   |
|                         | 8" BLACK OAK S 17° E 119.47' SCRIBED BT 6   |
|                         | 9" BLACK OAK N 29° W 84.63' SCRIBED BT 36   |

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner

FOUND 1 1/4" PIPE AT CORNER AND BRASS PLATE 33.05' S OF CORNER REPLACED 1 1/4" PIPE WITH 5/8" ROD AND REMON CAP

- 10" JACK PINE N66° E 69.96' BT 31
- 2" BLACK OAK S 35° E 62.42' TO SPIKE
- 9" BLACK OAK N 23° W 84.63'
- 2" BLACK OAK S 57° W 72.57' TO NAIL AND TAG

Signed by William E Woods Date 11-20-97  
 WILLIAM E. WOODS P.S.  
 Surveyor's Michigan License No. 25882



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983

**SURVEY & REMONUMENTATION**

MAR 18 1998

SECTION