

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FEB 15 2001

SECTION

For corners in IOSCO Located in: _____ Corner Code # _____

1. Public Land Survey	T	<u>24N</u>	R	<u>9E</u>	<u>C-1</u>
	T	<u>25N</u>	R	<u>9E</u>	<u>C-13 ALCONA</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	_____	_____	_____
	S	_____	_____	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
3. Miscellaneous Property in Sec.	S	_____	_____	_____	_____
	S	_____	_____	_____	_____
4. Lot No. _____, Recorded Plat _____					
5. Private Claims _____					

060 2000

STATE OF MICHIGAN
IOSCO COUNTY
FILED
15 DEC 2000 2:24:42 PM
BONITA M. COYLE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, WILLIAM E. WOODS P.S., in a field survey on OCT. 16, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded in this certificate.

Description of original monument and accessories and/or subsequent restoration:

1843: ORIGINAL GOVERNMENT NOTES

SET POST
Y. PINE 8" S79°E 1.18 CHAINS

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 10-11-2000
James H. Stranger

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

2000: WILLIAM E. WOODS

FOUND MONUMENT BOX WITH 1" SQUARE BOLT
THIS CORNER IS COMMON WITH C-13 T25N R9E TO THE NORTH
REPLACED 1" SQUARE BOLT WITH 5/8" REROD WITH REMON ALUMINUM CAP

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/8" REROD WITH REMON ALUMINUM CAP
EDAR POST 6" N3°E 33.33'
OPLAR 5" S25°E 53.31'
P. DUE SOUTH 32.26'
OPLAR 5" S46°W 56.53'



by William E Woods
WILLIAM E. WOODS P.S.
Surveyor's Michigan License No. 25882

Date 12-6-2000