


LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FEB 15 2001

SECTION

For corners in IOSCO Located In: Corner Code #
1. Public Land Survey T 24N R 9E E-1
2. Property Controlling in Section S
3. Miscellaneous Property in Sec. S
4. Lot No. Recorded Plat
5. Private Claims

062 2000



Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13. A dot is marked in the cell at row 1, column D.

I, WILLIAM E. WOODS P.S. ; in a field survey on OCT. 16 , 20 00 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1843: ORIGINAL GOVERNMENT NOTES

SET POST

TAMARACK 8" S52°E 34 LINKS
TAMARACK 7" S54°W 21 LINKS

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 10-11-2000

James H. Granger

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

2000: WILLIAM E. WOODS

FOUND 1" SQUARE BOLT IN MONUMENT BOX AT E-13 T25N R9E SET AT GOVERNMENT PROPORTIONATE 19.58 FEET WEST OF E-13 T25N R9E

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" ROD WITH REMON CAP IN MONUMENT BOX

P.P. N60°E 54.19'
POPLAR 6" S25°E 46.61'
POPLAR 6" S8°W 35.69'
HEMLOCK 6" S50°W 49.66'



Signed by William E Woods

Date 12-06-2000

WILLIAM E. WOODS P.S.

Surveyor's Michigan License No. 25882