

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

1999 IOSCO COUNTY REMONUMENTATION CORNER

For corners IOSCO Located In: _____ Corner Code# _____

1. Public Land Survey T 24N R 9E G-3
 T _____ R _____ _____
 T _____ R _____ _____
 T _____ R _____ _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____ , Recorded Plat _____

5. Private Claims _____

99-70

STATE OF MICHIGAN
DEEDS DEPARTMENT
FILED

22 DEC 99 2:41 P.M.

DOMITA M. GONIA
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, WILLIAM E. WOODS P.S. , in a field survey on DEC. 10 , 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1843: ORIGINAL GOVERNMENT NOTES

SET POST
TAMARACK 10° S69°E 16 LKS
TAMARACK 10° S17°W 15 LKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SET CORNER BY SINGLE PROPORTIONATE BETWEEN G-1 & G-10

ACCEPTED BY THE IOSCO COUNTY SURVEY REPAIR GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 10-13-99

James H. Branger

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" REBAR & REMON CAP

 SET NAIL & TAG N15°W 228.86' 30" W. PINE
 SET NAIL & TAG N40°E 207.53' 16" W. SPRUCE
 SET NAIL & TAG S20°E 140.38' 16" W. SPRUCE
 SET NAIL & TAG S65°W 95.35' 12" W. SPRUCE



Signed by William E Woods Date 12-15-99
 WILLIAM E. WOODS P.S.
 Surveyor's Michigan License No. 25882

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

APR 27 2000

SECTION