

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

1999 IOSCO COUNTY REMONUMENTATION CORNER

For corners IOSCO Located In: _____ Corner Code # _____

1. Public Land Survey	T <u>24N</u>	R <u>9E</u>	<u>G-4</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

99-67

STATE OF MICHIGAN
REGISTER OF DEEDS
FILED

22 DEC 99 2:41 P.M.

RONITA M. COBLE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, WILLIAM E. WOODS P.S., in a field survey on DEC. 10, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1843: ORIGINAL GOVERNMENT NOTES

SET POST

YELLOW PINE 8" N4°E 26 LKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SET CORNER BY SINGLE PROPORTIONATE BETWEEN G-3 & G-5

ACCEPTED BY THE IOSCO COUNTY SURVEY MEET GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 10-13-99

James H. Granger

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" REBAR & REMON CAP

SET NAIL & TAG S40°W 90.31' 30" W, PINE

SET NAIL & TAG N28°W 61.49' 12" W, SPRUCE

SET NAIL & TAG S70°E 111.57' 12" MAPLE

SET NAIL & TAG S8°E 146.79' 16" OAK



Signed by William E Woods

Date 12-15-99

WILLIAM E. WOODS P.S.

Surveyor's Michigan License No. 25882

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

APR 27 2000

SECTION