

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1999 IOSCO COUNTY REMONUMENTATION CORNER

For corners IOSCO Located In: _____ Corner Code # _____

1. Public Land Survey	T	<u>24N</u>	R	<u>9E</u>	G-5
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Sec.	S	_____	T	_____	R
	S	_____	T	_____	R
4. Lot No. _____, Recorded Plat _____					
5. Private Claims _____					

99-59

STATE OF MICHIGAN
IOSCO COUNTY
FILED

22 DEC 99 2:38 P.M.

RONITA N. COYLE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, WILLIAM E. WOODS P.S., in a field survey on DEC. 10, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1843: ORIGINAL GOVERNMENT NOTES

SET POST

MAPLE 8" S 33° W 26 LKS

YELLOW PINE 26" N 50° E 46 LKS

1970: R. L. MILLER

LAKWOOD SHORES GOLF & COUNTRY CLUB NO. 3

PLAT COMMENCES AT THIS CORNER LIBER 13 PAGES 30-32

1970: R. L. MILLER

LAKWOOD SHORES SUBDIVISION NO. 12

PLAT COMMENCES AT THIS CORNER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND PINCH PIPE AT POSITION SHOWN ON PLATS & WILL USE FOR G-5

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 10-13-99

James A. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED FOUND PINCH PIPE WITH A 5/8" BAR & REMON CAP

SET NAIL & TAG S 55° E 14.58' 10" MAPLE

SET NAIL & TAG SOUTH 11.87' 6" OAK

SET NAIL & TAG S 45° W 15.46' 6" WHITE PINE

SET NAIL & TAG N 15° E 21.80' 6" OAK

Signed by

William E. Woods

Date

12-22-99

WILLIAM E. WOODS P.S.

Surveyor's Michigan License No.

25882



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

REF

APR 21 2000

SECTION