

FEB 16 1999

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

REMONUATION CORNER

SECTION

For corners IOSCO Located In: Corner Code #

- 1. Public Land Survey T 24N R 9E G-7
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

4. Lot No. , Recorded Plat
5. Private Claims

98-57

STATE OF MICHIGAN
IOSCO COUNTY
FILED

10 DEC 98 2:56 P.M.

BONITA M. COYLE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Grid table with columns A-L and rows 1-13. Contains numbers 1-36 and a central dot.

I, WILLIAM E. WOODS P.S., in a field survey on NOV 17, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1843: ORIGINAL GOVERNMENT NOTES SET POST
6" SPR. PINE N 80° W 43 LK.
8" SPR. PINE S 55° E 25 LK.
1998: R.J. COOKE SUPERVISOR'S PLAT OF VERNON E RIX PARK LIBER 9 PAGES 39 & 40
1974: R.L. MILLER BOUNDARY SURVEY LIBER 235 PAGE 704
1975: R.L. MILLER BOUNDARY SURVEY LIBER 237 PAGE 632
1992: R.L. MILLER LCRC G-7 LIBER 92 PAGE 8

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND 3/4" PIPE & WITNESSES ON LCRC
REPLACED WITH 5/8 ROD & REMON CAP.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner

- 5/8 BAR & REMON CAP
8" POPLAR S 40° W 31.60
12" RED OAK N 78° W 34.73
3" RED OAK N 84° E 24.97
16" PINE S 18° E 12.33

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 74 OF 1970 AT A MEETING HELD ON 9-22-98

James H. Kranger

Signed by William E Woods Date 12-9-98
WILLIAM E. WOODS P.S.

Surveyor's Michigan License No. 25882