

FEB 16 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION		REMONUATION CORNER	
For corners <u>IOSCO</u>	Located In:	Corner Code #	
1. Public Land Survey	T <u>24N</u> R <u>9E</u>	<u>G-8</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

98-58

STATE OF MICHIGAN
 IOSCO COUNTY
 FILED

10 DEC 98 2:56 P.M.

BONITA M. COYLE
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, WILLIAM E. WOODS P.S., in a field survey on NOV 17, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1843: ORIGINAL GOVERNMENT NOTES
 - SET POST
 - 6" SPR. PINE N 80° W 43 LK.
 - 8" SPR. PINE S 55° E 25 LK.
 - 1958: JAMES L. SCOTT
 - INTERLAKE PARK SUBDIVISION LIBER 8 PAGE 38
 - 1964: J.C. MILLER
 - VAN ETTAN LAKESIDE GRAPHICALLY LIBER 11 PAGE (S) 27-29
 - 1972: J.G. CAMPBELL
 - BOUNDARY SURVEY LIBER 215 PAGE 610

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CORNER AS SHOWN ON PLAT & SURVEY VERIFIED POSITION & USED FOUND CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner

- 5/8" BAR & REMON CAP
- N 20° W 34.08 24" OAK NAIL & TAG
- N 20° E 33.19 10" WHITE PINE NAIL & TAG
- N 80° E 48.23 5" OAK NAIL & TAG
- S 30° E 17.31 6" OAK
- S 10° W 120.26 CONCRETE MONUMENT

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 346 OF 1990 AT A MEETING HELD ON 9-22-98

James H. Granger

Signed by William E Woods Date 12-9-98

WILLIAM E. WOODS P.S.

Surveyor's Michigan License No. 25882

