

SURVEY RECORDS

FEB 16 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

REMOUNATION CORNER

For corners IOSCO Located In: _____ Corner Code # _____

1. Public Land Survey	T <u>24N</u>	R <u>9E</u>	G-11
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

98-59

STATE OF MICHIGAN
IOSCO COUNTY
FILED

10 DEC 98 2:56 P.M.

BONITA M. COYLE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, WILLIAM E. WOODS P.S., in a field survey on NOV 17, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1958: R.J. COOKE VAN ETTAN CREEK ACRES NO. 1 LIBER 8 PG 35-36
 - 1959: R.J. COOKE MERKELVILLE NO. 2 LIBER 9 PG 15-16
 - 1960: R.J. COOKE VAN ETTAN CREEK ACRES NO. 2 LIBER 9 PG 37-38
 - 1962: R.J. COOKE VAN ETTAN CREEK ESTATES LIBER 10 PG 39-40
 - 1974: R.L. MILLER BOUNDARY SURVEY LIBER 233 PG 865
 - 1975: NORHTEAST LAND SURVEYS BOUNDARY SURVEY
 - 1977: R.L. MILLER LCRC CONCRETE MONUMENT FD LIBER 77 PG 18
- 1843: ORIGINAL GOVERNMENT NOTES
GOVERNMENT DID NOT SET THIS CORNER FROM SOUTH
THEY SET MEANDER CORNER AT 72.80 CHAINS AND
STOPPED GOVERNMENT SET THIS CORNER FROM WEST AT
80 CHAINS
SET POST 14" BIRCH N 60° W 21 LK.
10" BIRCH N 62° E 23 LK.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CONCRETE MONUMENT & RECORDED WITNESSES.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner
CONCRETE MONUMENT

- FND NAIL IN 14" BIRCH (DEAD) S15E 23.70
- FND NAIL IN 12" BIRCH (DEAD) S26W 24.70
- SET NAIL IN 14" RED PINE N08E 36.65
- SET NAIL IN 18" RED MAPLE SOUTH 29.71
- SET NAIL IN 6" CEDAR N64W 26.33
- SET NAIL IN 48" TWIN MAPLE S78E 31.74

ACCEPTED BY THE IOSCO COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER P.A.
345 OF 1990 AT A MEETING
HELD ON 9-22-98

James A. Krueger

Signed by William E. Woods Date 12-9-98
WILLIAM E. WOODS P.S.

Surveyor's Michigan License No. 25882