

FEB 16 1999

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970
REMONUATION CORNER

SECTION

For corners IOSCO Located In: _____ Corner Code # _____

1. Public Land Survey T 24N R 9E H-9
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

98-62

STATE OF MICHIGAN
 IOSCO COUNTY
 FILED
 10 DEC 98 2:57 P.M.
 BONITA H. COYLE
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, WILLIAM E. WOODS P.S., in a field survey on NOV 17, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1843: ORIGINAL GOVERNMENT NOTES SET POST
 14" Y. PINE S 69° W 70 LK.
 12" Y. PINE N 42° W 63 LK.
- 1915: H. BELNAP PLAT OF OSCODA BEACH LIBER 1 PAGE 28
- 1956: R.J. COOKE SUPERVISOR'S PLAT OF EAST BREWSTER PARK LIBER 7 PAGE 23 & 24
- 1957: R.J. COOKE PLAT OF VAN'S OAK RIDGE LIBER 7 PAGES 41 & 42

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CORNER AT POSITION SHOWN ON PLATS REPLACED WITH 5/8 ROD & REMON CAP.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 5/8" ROD & REMON CAP
- P.P. N82°E 36.50
- 6" OAK S10°W 17.50
- 12" W. PINE N55°W 37.90
- 12" DOUBLE OAK N25°W 55.55

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 74 OF 1970 AT A MEETING HELD ON 9-22-98

James H. Morgan



Signed by William E. Woods Date 12-9-98
 WILLIAM E. WOODS P.S.

Surveyor's Michigan License No. 25882