

FEB 18 1999

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

REMONUATION CORNER

SECTION

For corners 7IOSCO Located In: _____ Corner Code # _____

1. Public Land Survey T 24N R 9E H-11
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

98-63

STATE OF MICHIGAN
IOSCO COUNTY
FILED

10 DEC 98 2:57 P.M.

RONITA M. COYLE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, WILLIAM E. WOODS P.S., in a field survey on NOV 17, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1843: ORIGINAL GOVERNMENT NOTES SET POST
 12" Y. PINE S 79° W 44 LKS.
 10" Y. PINE N 68° W 40 LKS.
- 1944: R.J. COOKE WIER WOODLANDS SUBDIVISION LIBER 4 PAGES 26-28
- 1948: R.J. COOKE HUGHES OSCODA HEIGHTS LIBER 5 PAGE 14
- 1958: R.J. COOKE VAN ETTAN CREEK ACRES NO. 1 LIBER 8 PAGES 35-36
- 1959: R.J. COOKE MERKELVILLE NO. 1 LIBER 9 PAGES 7-8

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

CORNER WAS DUG OUT WHEN NEW MAN HOLE WAS PUT IN REPLACED CORNER FROM PLAT MONUMENTS.

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 373 OF 1990 AT A MEETING HELD ON 9-22-98

Jane H. Manger

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner

- 5/8 BAR WITH REMON CAP
- MON DUE WEST 38.35
- MON DUE EAST 111.22
- TOP. FIRE HYDRANT N 05° W 42.62
- 18" OAK S 66° W 64.34



Signed by William E. Woods Date 12-9-98
 WILLIAM E. WOODS P.S.
 Surveyor's Michigan License No. 25882