

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

1999 IOSCO COUNTY REMONUMENTATION CORNER

For corners IOSCO Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey      T 24N    R 9E      1-1  
    T \_\_\_\_\_    R \_\_\_\_\_      \_\_\_\_\_  
    T \_\_\_\_\_    R \_\_\_\_\_      \_\_\_\_\_  
    T \_\_\_\_\_    R \_\_\_\_\_      \_\_\_\_\_

2. Property Controlling    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    in Section                S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous            S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    Property in Sec.         S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_



STATE OF MICHIGAN  
 IOSCO COUNTY  
 FIDEL

22 DEC 99 2:39 P.M.

RONITA H. COLE  
 REGISTER OF DEEDS

**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

1. WILLIAM E. WOODS P.S. , in a field survey on DEC. 10 , 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 1843: ORIGINAL GOVERNMENT NOTES      SET POST

1946: ORE F. GOULD      WHITE BIRCH 10" S 11° W 39 LKS  
    BLACK ASH 3" S 53° E 24 LKS  
    LAKE HURON SAND BEACH SUBDIVISION  
    PLAT COMMENCES AT THIS CORNER  
    LIBER 4 PAGES 42-43

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND REMON CAP AT CORNER COMMON WITH SECTIONS TO NORTH, WILL RECORD FOUND CORNER.


ACCEPTED BY THE IOSCO COUNTY  
 SURVEY PEER GROUP AS THE  
 OFFICIAL CORNER UNDER P.A.  
 345 OF 1990 AT A MEETING  
 HELD ON 10-13-99  
*James H. Thayer*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner

CONCRETE MONUMENT WITH ALCONA COUNTY REMON CAP

N 20° E 8" CEDAR 48.61'  
 N 40° W 5" HEMLOCK 16.80'  
 N 72° W 7" TWIN CEDAR 15.38'  
 SOUTH 10" ASH 14.69'

Signed by *William E Woods* Date 12-15-99  
 WILLIAM E. WOODS P.S.  
 Surveyor's Michigan License No. 25882



FORM APPROVED BY MICHIGAN STATE  
 BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983

REF  
 APR 27 2000  
 SECTION