

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1999 IOSCO COUNTY REMONUMENTATION CORNER

For corners IOSCO Located In: _____ Corner Code # _____

1. Public Land Survey T 24N R 9E I-2
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

99-69

STATE OF MICHIGAN
 IOSCO COUNTY
 FIELD

22 DEC 99 2:41 P.M.

RONITA M. DUNLE
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, WILLIAM E. WOODS P.S., in a field survey on DEC. 10, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1843: ORIGINAL GOVERNMENT NOTES

SET POST

HEMLOCK 8" N73°E 11 LKS

WHITE BIRCH 10" N87°W 11 LKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CONCRETE MONUMENT AT POSITION SHOWN ON PLAT FOR EAST 1/4 CORNER

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1980 AT A MEETING HELD ON 10-13-99

James H. Ganger

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner

SET 1/2" BAR & CAP INSIDE 3/4" PIPE IN MONUMENT

SET NAIL & TAG NORTH 6.03' 12" ASH

SET NAIL & TAG S70°E 25.86' 10" TWIN MAPLE

SET NAIL & TAG S30°W 22.18' 2" WHITE PINE

SET NAIL & TAG N75°W 21.66' 20" MAPLE



Signed by William E. Woods

Date 12-15-99

WILLIAM E. WOODS P.S.

Surveyor's Michigan License No. 25882

FORM APPROVED BY MICHIGAN STATE
 BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

RFI

420 2000

SECTION