

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1999 IOSCO COUNTY REMONUMENTATION CORNER

For corners IOSCO Located In: _____ Corner Code # _____

1. Public Land Survey T 24N R 9E I-3 _____
 T _____ R _____ _____
 T _____ R _____ _____
 T _____ R _____ _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

99-68

STATE OF MICHIGAN
 IOSCO COUNTY
 FILED

22 DEC 99 2:41 P.M.

DORITA M. COYLE
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, WILLIAM E. WOODS P.S., in a field survey on DEC. 10, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1843: ORIGINAL GOVERNMENT NOTES. SET POST CEDAR 6" S57°E 18 LKS WHITE PINE 18" S12°W 23 LKS
 1946: ORE F. GOULD LAKE HURON SAND BEACH SUBDIVISION 20 FEET NORTH OF THE SW CORNER OF LOT 71 LIBER 4, PAGES 42-43
 1966: JOHN C. MILLER LAKEWOOD SHORES SUBDIVISION PLAT COMMENCES AT THIS CORNER LIBER 11 PAGES 46-47
 1966: JOHN C. MILLER LAKEWOOD SHORES SUBDIVISION NO. 1 PLAT COMMENCES AT THIS CORNER LIBER 11 PAGE 50
 1996: WILLIAM E. WOODS SURVEY DONE BY NORTHEAST LAND SURVEYS SURVEY COMMENCES AT THIS CORNER LIBER 508 PAGE 946

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FOUND 1 1/2" PIPE AT POSITION SHOWN ON PLATS WILL USE FOR I-3

ACCEPTED BY THE IOSCO COUNTY SURVEY FIELD GROUP AS THE OFFICIAL CORNER UNDER P.A. 945 OF 1990 AT A MEETING HELD ON 10-13-99

James H. Sawyer

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner

SET 5/8" BAR & REMON CAP

 SET NAIL & TAG SOUTH 39.30' 7" MAPLE
 SET NAIL & TAG S70°W 7.79' 8" MAPLE
 S60°E 59.95' N.W. CORNER BRICK HOUSE
 SET NAIL & TAG N30°W 4.58' 6" ASH



Signed by William E Woods Date 12-15-99
 WILLIAM E. WOODS P.S.
 Surveyor's Michigan License No. 25882

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

REF
 480 2000
 SECTION