

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FEB 15 2001

SECTION

071 2000

STATE OF MICHIGAN
IOSCO COUNTY
FILED
15 DEC 2000 2:24:42 PM
BONITA M. COYLE
REGISTER OF DEEDS

For corners in IOSCO Located in: Corner Code #

1. Public Land Survey T 24N R 9E I-6
2. Property Controlling in Section S S T R
3. Miscellaneous Property in Sec. S
4. Lot No. Recorded Plat

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13. Cell 6-14 contains a black dot.

5. Private Claims

I, WILLIAM E. WOODS P.S., in a field survey on OCT. 16, 2000, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1843: ORIGINAL GOVERNMENT NOTES

SET POST
TAMARACK 4" S85°E 38 LKS.
CEDAR 10" S57°W 24 LKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

2000: WILLIAM E. WOODS

EXTENDED EAST LINE OF SECTION 10 SOUTH 40 CHAINS

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 10-11-2000
James H. Granger



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" BAR & REMON CAP

J. PINE 4" S17°W 7.48' NAIL & TAG
W. PINE 8" S78°W 12.17' NAIL & TAG
ASH 3" N50°W 10.08' NAIL & TAG
W. PINE 8" NORTH 24.88' NAIL TAG

Signed by William E Woods
WILLIAM E. WOODS P.S.

Date 12-06-2000

Surveyor's Michigan License No. 25882