

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

FEB 15 2001

SECTION

065 2000

STATE OF MICHIGAN
IOSCO COUNTY
FILED
15 DEC 2000 2:24:42 PM
BONITA M. COYLE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 in a grid pattern.

Form with fields: For corners in IOSCO, Located In: Corner Code #, 1. Public Land Survey, 2. Property Controlling in Section, 3. Miscellaneous Property in Sec., 4. Lot No., 5. Private Claims.

I, WILLIAM E. WOODS P.S., in a field survey on OCT. 16, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1843: ORIGINAL GOVERNMENT NOTES

SET POST 36.07 CHAINS WEST OF G-7
W. OAK 10° N1°E 11 LKS

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 10-11-2000

James H. Granger (Signature)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1960: R.J. COOKE

"SUPERVISOR'S PLAT OF VERNON E. RIX PARK" SHOWS SECTION LINE FROM G-7 TO POINT OF BEGINNING OF PLAT

2000: WILLIAM E. WOODS

RETRACED SECTION LINE AS PER PLAT "VERNON E. RIX PARK" MEASURED 2308 FEET TO WATER'S EDGE, GOVERNMENT M.C. WAS SET AT 2380.62 FEET APPROXIMATE 71 FEET OUT INTO LAKE WILL. SET REFERENCE CORNER 150.74 FEET EAST OF MEANDER CORNER ON SHORE OF VAN ETTAN LAKE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner. 5/8" BAR & REMON CAP REFERENCE CORNER 150.74 FEET EAST OF MEANDER CORNER 2229.88 WEST OF G-7

- OAK 14" S65°E 19.41' NAIL & TAG
W. OAK 16" N70°E 19.73' NAIL & TAG
SPRUCE 6" N15°E 36.52' NAIL & TAG
N.W. CORNER STEEL SEAWALL N40°W 21.85'
E. EDGE STEEL SEAWALL S65°W 5.18'

Signed by

William E Woods (Signature)

WILLIAM E. WOODS P.S.

Date

12-06-2000

Surveyor's Michigan License No. 25882

