

LAND CORNER RECORDATION CERTIFICATE

FEB 2 2 1996

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 24N N. 6E S., R. E. W.	K9
2. PROPERTY CONTROLLING IN SECTION	T. N. S., R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S., R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

STATE OF MICHIGAN  
IOSCO COUNTY  
FILED

29 NOV 95 12:20 P.H.

BONITA H. COYLE  
REGISTER OF DEEDS

95-07

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Patrick R. Leemon do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on April, 17 1995, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:  
**Section Corner common to Sections 23, 24, 25 and 26 of T24N R6E**

1845 GLO survey by James Mullett Set wood post, (1) Cedar 9 N18W 23 links, (2) Cedar 10 S25E 31 links  
 1909 survey by Fargo Eng. Co. Found one 1844 witness and set a wood post. (3) Cedar 10 N17-30E 13 links,  
 (4) Cedar 12 S75W 34 links  
 1927 GLO Dependent Resurvey by Guy Veal Found the wood post by Fargo and witness 2 thru 4 and replaced it w/ a 2"x36" iron pipi w/ brass cap, (5) Cedar 12 N48-30E 33 links, (6) Cedar 10 S60E 26 links, (7) Spruce 5 S81-30W 20 links,  
 (8) Cedar 10 N36-45W 17 links  
 1981 survey by H.W.D. for Consumers Power Co. Found the GLO brass cap monu., (9) Cedar 5 SW 9.79 ft., (10) Cedar 5 NW 25.81ft., (11) Cedar 7 SSE 24.96 ft.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I found the GLO brass cap monument in good condition and in the swamp about 500 feet south of the centerline of the NE-SW pavement. Witnesses 1 through 4 and 9 through 11 are gone. Witness 6 through 8 are dead and down. Witness 5 is dying and leaning. The distance to the N1/4 26 was found to be 2623.97 feet when checked against the GLO distance of 2625.15.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**Section Corner common to Sections 23, 24, 25 and 26 of T24N R6E**

I left the 2" x 36" iron pipe GLO brass cap iron as found  
 B.Ash 7 N14E 9.70 feet  
 B.Ash 9 S30E 7.04 feet  
 B.Ash 8 S62W 4.32 feet  
 Balsam Fir 5 N78W 16.10 feet  
 Fiberglass Post West 1.0 feet.

ACCEPTED BY THE IOSCO COUNTY  
 SURVEY PEER GROUP AS THE  
 OFFICIAL CORNER UNDER P.A.  
 345 OF 1990 AT A MEETING  
 HELD ON 10-31-95

*James H. Kravitz*

SIGNED BY Patrick R. Leemon DATE May 30, 1995

SURVEYOR'S MICHIGAN REGISTRATION NO. 31595

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_