

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

DICKINSON COUNTY

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY-----	T. 41 N. X, R. 30 W. <input checked="" type="checkbox"/>	A9
2. PROPERTY CONTROLLING IN SECTION 30-----	T. 41 N. X, R. 30 W. <input checked="" type="checkbox"/>	3, Meander Corner
3. MISCELLANEOUS PROPERTY IN SECTION-----	T.----- N. S, R.----- E. W. <input type="checkbox"/>	
4. LOT NO.-----, RECORDED PLAT-----		
5. PRIVATE CLAIMS-----		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on See below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner A9: Original monument and accessories not found.
 Corner 3: Not set on original survey nor subsequently apparently
 Meander corner between 3 and A10: Original monument and accessories not found.
 River is considerably higher than original due to dams.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner A9: Restored at record distance east of original 1/4 corner 1/2 mile west and record distance south of original section corner 2 miles north. This position seems to fit the best with land calls and distance east to corners.
 Corner 3: Established at record distance and on projected line from corners north.
 Meander Corner: Established on north bank Menominee River on projected line from north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner A9: Set 1" I.D. x 32" I.P. w/ 4" alum. cap. 5" Sugar N79W 33.4 ft. S24, NBT 5" W. Pine N40E 19.0 ft. S19, NBT 7" Sugar S80E 35.4 ft. S30, NBT Corner 3: Set 1" I.D. by 32" I.P. w/ 4" alum. cap. 10" Spruce N22E 17.7 1/16S, BT 4" W. Pine N80W 18.8 ft 1/16S, BT 4" Maple S48E 26.3 ft. 1/16S, BT	Meander corner: Set 1" I.D. by 32" I.P. w/4" alum. cap. 8" Ash N50E 9.7 ft MC, NBT 8" Ash N49W 14.5 ft MC, NBT 5" Spruce S72E 7.5 ft MC, NBT
--	---


SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 6-29-83
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. 19006