

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S <u>4</u> T <u>41N</u> R <u>31W</u>	<u>6</u>	
	S _____ T _____ R _____	(GCDB 360660)	
	S <u>3</u> T <u>41N</u> R <u>31W</u>	<u>H2</u>	
	S _____ T _____ R _____	(GCDB 440640)	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4			2			1	
3													
4	7		8			9		10	11			12	
5													
6	18		17			16		15	14			13	
7													
8	19		20			21		22	23			24	
9													
10	30		29			28		27	26			25	
11													
12	31		32			33		34	35			36	
13													

I, Stephan J. Szyszkoski, in a field survey on 01/21/16 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(6-Sec. 4) Northeast 1/16 corner, Section 4. Not previously monumented.

(H2) Center of Section 3. 1978- Established by E.Kazianka RLS at the intersection of 1/4 lines. Rec. in 1979 Liber 1 Page 576. Set 1" iron pipe with plastic cap. Maple 9" N80°W 22.1', Yellow Birch 8" N35°E 15.2'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(6-Sec. 6) Established the position for the corner at the intersection of straight lines connecting opposite 1/16 corners. Of those, only 1/16 corner #9 is currently monumented.

(H2) Found the 1978 monument in good condition but with deteriorated plastic cap. The position conforms to monumented G2 and 1/16 #8 to the west and to 1/4 corners H1 and H3. The 1978 witnesses are at record bearing and distance. The Y.Birch is in good condition, the Maple is a stump. I accept the position of the monument as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(6) Set 1"IDx28" I.pipe with 2" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 6" Spruce N55°E 27.9' mrkd "1/16S BT"
 10" Spruce S74°E 17.9' do
 4" Balsam S83°W 7.6' do
 10" Spruce N42°W 12.85' do
 Set sq'd spruce post adjacent.
 E= 7908204.856 N= 133934.087

(H2) Found 1"ID Iron pipe of record. Set new plastic cap #33986 in the top of same. Set measuring nail with MDNR tag in the side of:
 9" Y.Birch N38°E 15.25' old blazes (1978 BT)
 4" Maple N73°E 20.35' mrkd "C1/4 BT"
 4" Sugar S33°E 11.5' do
 5" Sugar S79°W 12.6' do
 E= 7909406.386 N= 133511.430

Bearings are magnetic. Coordinates are MCS83 in meters, NAD83(2011) Epoch 2010.00 datum
 Coord. Ref.=NGS PID RL0240: N= 145070.966 m. E= 7907633.632 m.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 02/25/2016

For the Michigan Department of Natural Resources, Forest Resources Division

