

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T ___ R ___		
	T ___ R ___		
	T ___ R ___		
2. Property Controlling in Section	S ___ T ___ R ___		
	S <u>9</u> T <u>41N</u> R <u>31W</u>	<u>7</u>	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___		
	S ___ T ___ R ___		
4. Lot No. _____, Recorded Plat _____			
5. Private Claims			

Register of Deeds Stamp & File
Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Oct 05 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(7-Sec. 9) North 1/16 corner between Sections 9 and 10. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(7-Sec. 9) Established the corner midway and on line between Section corner 1322.38' north and Quarter corner 1322.38' south. From the position thus established, I found a 1 1/4" ID iron pipe, projecting 4' above ground, S83E 9.8' distant, which I did not accept as marking the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(7) Set 1" ID x 32" I. pipe with 4" alum.
 MDNR cap. Set measuring nails in:
 6" Sugar N45E 31.6' mrkd "1/16S BT"
 13" Hemlock S45E 26.9' do
 9" Hemlock S05E 9.0' do
 4" twin Spruce N30W 20.9' do
 Set sq'd cedar post adjacent. Bearings
 are magnetic. Distances are to nail
 with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 10/16/06

For the Michigan Department of Natural Resources, Office of Land and Facilities