

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

**IRON COUNTY**

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 41 N. R. 31 E. W.	G2, G3
2. PROPERTY CONTROLLING IN SECTION 3	T. 41 N. R. 31 E. W.	10'
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Keith Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 4-11, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner G2: Original monument and accessories not found. Found Wisc. - Mich. Power Company Monument.
  - Corner G3: Original monument and accessories not found. Found Wisc. - Mich. Power Company Monument.
  - Corner 10: Not set on original survey nor subsequently apparently.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner G2: Restored at Wisc. - Mich. Power Company Monument
  - Corner G3: Restored at Wisc. - Mich. Power Company Monument
  - Corner 10: Established Midway and on line between corners north and south.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- |  |   |
|--|---|
| <p>Corner G2: 2" I.D. by unknown length I.P. with 3" Brass Cap.<br/>4" maple N23W 16.6 Ft. 1/4S, NBT<br/>5" maple S63E 10.2 Ft. 1/4S, NBT<br/>5" maple S71W 19.7 Ft. 1/4S, NBT</p> | <p>Corner G3: 2" I.D by unknown length I.P. with 3" Brass Cap.<br/>5" sugar N35E 18.7 Ft. S3, NBT<br/>5" sugar S05W 21.0 Ft. S9, NBT<br/>7" sugar S71W 12.2 Ft. S4, NBT</p> |
| <p>Corner 10: Set 1" I.D. by 30" I.P. with 4" alum. cap.<br/>5" sugar S02W 10.9 Ft. 1/16S, BT<br/>5" sugar N86W 8.6 Ft. 1/16S, BT</p>  | <p>5" sugar N21E 17.3 Ft. 1/16S, BT<br/>5" sugar N67W 4.3 Ft. Squared</p>   |

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE 8-17-84  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett  
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

