

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

IRON COUNTY

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____	
2. PROPERTY CONTROLLING IN SECTION-- 3	T. 41 N. _____ E. _____ S. _____ R. 31 W. _____	8, 5, 2	
3. MISCELLANEOUS PROPERTY IN SECTION--	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____	
4. LOT NO. _____, RECORDED PLAT _____			
5. PRIVATE CLAIMS _____			

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 4-17-84, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner 8: Not set on original survey nor subsequently apparently.
- Corner 5: Not set on original survey nor subsequently apparently.
- Corner 2: Not set on original survey nor subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner 8: Established midway and on line between center 1/4 corner and the west 1/4 corner.
- Corner 5: Established midway and on line between center 1/4 corner and north 1/4 corner.
- Corner 2: Established midway and on line between section corner east and 1/4 corner west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|--|
| Corner 8: Set 1" I.D. by 32" I.P. w/4" alum. cap.
7" maple N23E 9.7 ft 1/16S, BT
5" sugar S67E 7.9 ft 1/16S, BT
7" sugar S38W 19.2 ft 1/16S, BT | Corner 2: Set 1" I.D. by 32" I.P. w/4" alum. cap.
7" ash N10W 22.9 ft 1/16S, BT
7" w. birch N23E 13.1 ft 1/16S, BT
5" w. birch S15E 14.4 ft 1/16S, BT |
|--|--|
- Corner 5: Set 1" I.D. by 32" I.P. w/4" alum. cap.
 5" sugar S87E 21.3 ft 1/16S, BT
 4" sugar N11E 19.0 ft 1/16S, BT
 6" sugar S21E 7.0 ft 1/16S, BT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

DATE 8-17-84

Keith L. Sackett
 Michigan Department of Natural Resources
 19006



SURVEYOR'S MICHIGAN REGISTRATION NO. _____