

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

IRON COUNTY

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 41 N. R. 31 XX W.	M8, M6, M7
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S. R. _____ E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 6-7- 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
 Corner M8: Original monument and accessories not found.
 Corner M6: Original monument and accessories not found. Found 2" I.D. by unknown length I.P. Set by unknown person.
 Corner M7: Original monument and accessories not found.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 Corner M8: Restored on line between section corners north and south.
 Corner M6: Restored at Iron Pipe. It agrees fairly well with other corners in area as to bearing and distance.
 Corner M7: Restored on line between section corners north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Corner M8: Set 1" ID x 32" I.P. w/4" alum. cap.
 8" Spruce N46W 37.7 ft., 1/4 S, NBT
 10" Balsam N30E 17.1 ft., 1/4 S, NBT
 7" W. Pine S21W 37.1 ft., 1/4 S, NBT
 Corner M6: 2" I.D. by unknown, length Iron Pipe.
 3" Sugar N53W 13.5 ft., 1/4S, NBT
 6" Sugar S35W 30.6 ft., 1/4S, NBT
 9" Sugar S46E 30.9 ft., 1/4S, NBT
 Corner M7: Set 1" I D by 32" I.P. w/4" alum. cap.
 5" Sugar S01W 6.5 ft. S 24, NBT
 7" Sugar N10E 11.0 ft. S 18, NBT
 4" Sugar N34W 14.2 ft. S13, NBT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)
 FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett CHIEF OF SURVEY/PARTY DATE 6-29-83
 MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

