

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Iron

_____	Located In:	Corner Code #/
(County)		
1. Public Land Survey	T 41N R 31W	A1
	T _____ R _____	A2
	T _____ R _____	
	T _____ R _____	
2. Property Controlling In Section	S 6 T _____ R _____	2
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21	22	23	24				
7													
8	16	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Keith Backett, in a field survey on See below, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


A1	A2	2
Original monument and accessories not found.	Original monument and accessories not found.	Not set on original survey nor subsequently, apparently.
Found	Found	Found
old rotted post.		

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A1	A2	2
11-12-87	11-10-87	11-10-87
Restored by double proportion.	Restored midway on line.	Established midway on line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A1	A2	2
Set 1" I.D. x 32" I.P. w/4" aluminum cap.	Set 1" I.D. x 32" I.P. w/4" aluminum cap.	Set 1" I.D. x 32" I.P. w/4" aluminum cap.
5" sugar N06E 13.5' 831 NBT	8" maple 826E 14.5' 1/48 NBT	4" maple 830N 1.1' 1/168 BT
9" maple N68W 28.8' 836 NBT	5" sugar 862W 22.4' 1/48 NBT	12" spruce 875E 7.6' 1/168 BT
4" maple 867E 13.2' 86 NBT	12" white birch N37W 31.3' 1/48 NBT	5" maple N29W 25.7' 1/168 BT



Signed by Keith Backett Date 2-26-88

Surveyor's Michigan License No. 19006