

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| | | | |
|----------|---------------------------------|----------------------------|-----------------------|
| 1 | Iron | Located In: | Corner Code ## |
| | (County) | | |
| 1. | Public Land Survey | T <u>41N</u> R <u>31W</u> | <u>C4</u> |
| | | T _____ R _____ | <u>D5</u> |
| | | T _____ R _____ | |
| | | T _____ R _____ | |
| 2. | Property Controlling in Section | S <u>7</u> T _____ R _____ | <u>10</u> |
| | | S _____ T _____ R _____ | |
| 3. | Miscellaneous Property in Sec. | S _____ T _____ R _____ | |
| | | S _____ T _____ R _____ | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Keith Sackett, in a field survey on October 25, 19 90, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | | | | | | | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | | | | | | | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:


| | | |
|---|---|--|
| <u>C4</u> | <u>D5</u> | <u>10</u> |
| Original monument and accessories not found. Found Michigan-Wisconsin monument. | Original monument and accessories not found. Found Michigan-Wisconsin monument. | Not set on original survey nor subsequently, apparently. |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

| | | |
|--|--|--|
| <u>C4</u> | <u>D5</u> | <u>10</u> |
| Restored at Michigan-Wisconsin monument. | Restored at Michigan-Wisconsin monument. | Established on line by proportion between corners. |

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| | | |
|--|--|--|
| <u>C4</u> | <u>D5</u> | <u>10</u> |
| Found Michigan-Wisconsin Power Co. monument. | Found Michigan-Wisconsin Power Co. monument. | Set 10-29-90, 1" ID x 32" iron pipe v/4" aluminum cap. |
| 12" spruce S73E 5.0' 1/4s, NBT | 6" sugar W28E 20.7' 1/4s, NBT | 5" sugar N12W 2.3' 1/16s, BT |
| 8" spruce N82W 3.9' 1/4s, NBT | 5" sugar S23W 15.9' 1/4s, NBT | 8" sugar S01E 10.9' 1/16s, BT |
| 10" maple S28W 15.1' 1/4s, NBT | 4" sugar W73W 14.7' 1/4s, NBT | 4" sugar S57W 18.7' 1/16s, BT |
| | | 4" sugar N37E 1.8' squared |



Signed by Keith Sackett Date November 14, 1990

Surveyor's Michigan License No. 19006