

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
T Iron

	(County)	Located in:	Corner Code #
1. Public Land Survey		T <u>41E</u> R <u>31W</u>	<u>A5</u>
		T _____ R _____	<u>C5</u>
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling in Section	S <u>7</u>	T _____ R _____	<u>14</u>
	S _____	T _____ R _____	_____
3. Miscellaneous	S _____	T _____ R _____	_____
Property in Sec.	S _____	T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

I, Keith Sackett, in a field survey on October 29, 1990, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


A5	C5	14
Original monument and accessories not found. Found Wisconsin-Michigan Power Co. monument.	Original monument and accessories not found. Found Wisconsin-Michigan Power Co. monument.	Not set on original monument nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A5	C5	14
Restored at Wisconsin-Michigan Power Co. monument.	Restored at Wisconsin-Michigan Power Co. monument.	Established midway and on line.

C. Description of monument for corner and accessories established to perpetuate localing the position of the corner:

A5	C5	14
Found Wisconsin-Michigan Power Co. monument. 18" oak S43W 13.8' S13 NBT 6" sugar N10W 18.9' S12 NBT 6" sugar N80E 24.0' S7 NBT Squared 5" sugar south 2.3 ft.	Found Wisconsin-Michigan Power Co. monument. 4" sugar N40E 24.3' S8 NBT 10" sugar N25W 12.5' S7 NBT 5" sugar S35E 6.7' S17, NBT	Set 1" ID x 32" iron pipe w/4" aluminum cap. Corner falls in the right-of-way of power line. 14" hemlock N12E 81.8' 1/16s, BT 10" hemlock S51E 58.7' 1.16s, BT 6" sugar N86W 85.7' 1/16s, BT



Signed by Keith Sackett Date November 14, 1990

Surveyor's Michigan License No. 19006