

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>41N</u> R <u>32W</u>	<u>H3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S <u>2</u> T <u>41N</u> R <u>32W</u>	<u>4</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims

4 Sep 13 2006  
 H3 Sep 11 2006

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2		1	
3													
4	7		8			9		10		11		12	
5													
6	18		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(H3) Quarter corner common to Sections 3 and 10. 1978 - Remonumented from the burned stump of an original Y.Pine BT by A.O.Enger RLS. Set 1"IDx36" I.pipe with 3 3/4" aluminum cap. Witnesses: Red Maple 5 N50E 16.4', Red Maple 5 S17W 16.7'.  
 (4-Sec. 2) Northwest 1/16 corner, Section 2. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H3) Recovered the 1978 monument in good condition and at record bearing and distance from the remaining 1978 N8T Maple N54E in good condition. Left the monument in place and made new witnesses as described below.  
 (4-Sec. 2) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H3) Fd. 1"ID I.pipe with 3 3/4" alum. MDNR cap. Set measuring nails in: 7" Maple N54E 16.8' old blazes * 5" Maple N05E 26.0' mrkd "1/4S NBT" 6" Maple N55W 26.6' do 7" Maple S29W 34.3' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. * denotes 1978 NBT.	(4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 8" Spruce N47E 19.4' mrkd "1/16S BT" 4" Spruce S09E 37.8' do 7" Spruce S30W 48.2' do 4" Cherry N87W 12.7' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.
---	--



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 9/26/06

For the Michigan Department of Natural Resources, Office of Land and Facilities