LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron
(County)

	Located In:			Corner Code #
1. Public Land Survey		T 41N	R 32W	J4
		T	R	
		T	R	
	S	T	R	
2. Property Controlling	S 4	T 41N	R 32W	8
in Section	S	T	R	
3. Miscellaneous	S	T	R	
Property in Sec.	S	T	R	

Register of Deeds Stamp & File Number

4. Lot No. _____ , Recorded Plat_____
5. Private Claims



Sep 06 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20 ____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(J4) Center of Section 11. Not established in the original survey.
(8-Sec. 4) West 1/16 corner, Section 4. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J4) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.
(8-Sec. 4) Established the corner midway and on a straight line between Quarter corner 1320.33' west and Center of Section 1320.33' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
6" Maple S67E 13.3' mrkd "C1/4 BT"
6" triple Maple N10E 6.1' do
12" Oak S35E 26.3' do
6" Maple S86W 19.9' do
Set sq'd maple post adjacent. Bearings are magnetic. Distances are to nail with tag.

(8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
16" R.Pine N18W 47.6' mrkd "1/16S BT"
9" twin Oak N33E 18.0' do
9" twin Oak S67W 24.5' do
10" twin Oak N83W 22.6' do
Set sq'd R.Pine post adjacent. Bearings are magnetic. Distances are to nail with tag.

STATE OF MICHIGAN
STEPHAN J. SZYSZKOSKI
LAND SURVEYOR
No. 33986
LICENSED LAND SURVEYOR

Signed by Stephan J. Szyszkoski

Date 9/26/06

Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
Revised May 14, 1975
Revised Jan., 1983
Rervised Oct., 1995