

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Iron <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>41N</u> R <u>32W</u>	J5
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S <u>4</u> T <u>41N</u> R <u>32W</u>	<u>7</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File  
Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Sep 18 2006

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(J5) Quarter corner common to Sections 11 and 14. 1977 - A.O.Enger RLS restored the corner position by single proportionate measurement between corner I5 and a W.Pine line tree stump 10.892 chains east of J5. Mr. Enger set a 1" ID x36" iron pipe with 3 3/4" aluminum cap. Witnesses: Cheselled "+" in a boulder N56W 14.7', Elm 11 (may be dead) S71W 40.2'.  
 (7-Sec. 4) North 1/16 corner between Sections 3 and 4. 1978 - Corner established by A.O.Enger RLS midway and on line between Section corner to north and Quarter corner to south. Mr. Enger placed a 1"IDx36" iron pipe with 3 3/4" aluminum cap. Witnesses: Red Oak 6 N50E 6.9', Red Oak 6 N85W 20.8'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J5) Recovered the 1977 monument in good condition and at record bearing and distance from the chiselled "+" witness, found in good condition. Left the monument in place and made new witnesses as described below.  
 (7-Sec. 4) Recovered the 1978 monument in good condition and at record bearing and distance from the remaining 1978 witness Red Oak NW in good condition. My measurements show that the monument is located S14W 0.24' from the midpoint position intended in 1978 and I accept the monument as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J5) Fd. 1" ID I.pipe with 3 3/4" alum. MDNR cap. Fd. Chis "+" in boulder N53W 14.7' Set measuring nails in: 16" Poplar N25E 7.0'    mrkd "1/4S NBT" 9" Poplar S67E 28.2'    do 9" Poplar N70W 11.7'    do Fd. sq'd cedar post adjacent. Bearings are magnetic. Distances to trees are to nail with tag in side of tree.	(7) Fd. 1"ID I.pipe with 3 3/4" alum. MDNR cap. Set measuring nails in: 7" Oak N80W 21.0'    old blazes * 8" Oak N41E 7.7'    mrkd "1/16S BT" 10" Oak S28E 20.0'    do 5" Maple clump S35W 41.4'    do Sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. * denotes 1978 NBT.
---	---



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 9/26/06

For the Michigan Department of Natural Resources, Office of Land and Facilities