

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
<small>(County)</small>		
1. Public Land Survey	T <u>41N</u> R <u>32W</u>	<u>K3</u>
	T <u>41N</u> R <u>32W</u>	<u>K4</u>
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3											●		
4	7		8		9		10		11		●	12	
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Sep 06 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K3) Corner common to Sections 1-2-11-12. 1978 - Arthur O. Enger RLS recovered and accepted a Wisconsin-Michigan Power Company concrete monument with 3"x3" square brass tablet marking the position for the corner. 1978 witnesses: Sugar Maple 5 N88W 27.4', Basswood 6 S87E 12.6', Y.Birch 6 N31E 10.0'.

(K4) Quarter corner common to Sections 11 and 12. 1978 - Arthur O. Enger RLS recovered and accepted a Wisconsin-Michigan Power Company concrete monument marking the position for the corner. 1978 witnesses: Red Maple 6 N36E 27.8', Red Maple 6 S55E 17.6'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K3) Recovered the WMPCO monument described in the 1979 record filed by Mr. Enger, a 7" x 11" tall right-rectangular concrete pyramid with brass tablet affixed, in good condition, and at record bearing and distance from the three 1978 witnesses. The Basswood and Sugar Maple NBTs are in good condition. The Y. Birch NBT is a standing dead stub. Left the monument in place and made new witnesses as described below.

(K4) Recovered the WMPCO monument described by Mr. Enger, a 7" right-rectangular concrete pyramid with 3" square brass tablet affixed, in good condition, and at record bearing and distance from the 1978 witnesses. The R.Maple NE is in good condition. The R.Maple SE is dead. Left the monument in place and made new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K3) Found WMPCO concrete monument with brass tablet. Set measuring nails in:
 6" Basswood S83E 12.8' old blazes *
 5" Sugar N85W 27.5' do *
 5" Sugar S70W 31.9' wrkd "S11 NBT"
 6" Maple N24W 26.1' "S2 NBT"
 Fd. sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. * denotes 1978 NBT.

(K4) Fd. WMPCO conc. monument with 3" brass tablet. Set measuring nails in:
 7" Maple N40E 28.1' old blazes *
 9" Sugar S62E 25.0' wrkd "1/4S NBT"
 8" Oak S18W 29.3' do
 5" Oak N89W 13.3' do
 Set sq'd oak post adjacent. Bearings are magnetic. Distances are to nail with tag. * denotes 1978 NBT.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 9/26/06