

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Iron	Located In:	Corner Code #
<small>(County)</small>		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S 4 T 41N R 32W	2
	S 4 T 41N R 32W	9
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims

9 Sep 18 2006  
 2 Sep 14 2006

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- (2-Sec. 4) East 1/16 corner between Section 4 T41N-R32W and Section 33 T42N-R32W. 1971 - Established by A.O. Enger RLS midway and on line between Quarter and Section corners. Set 1"IDx36" iron pipe with 4" aluminum cap. Sugar Maple 5 N19E 15.5', White Birch 7 N50W 32.9'.
- (9-Sec. 4) East 1/16 corner, Section 4. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (2-Sec. 4) Recovered the 1971 monument in good condition and at record bearing and distance from the 1971 BTs. The Maple NE is not a Sugar Maple but is a Red Maple in good condition. The Birch NW is now a rotting stump. The monument is located S12W 0.62' from the midway position intended in 1971 and I accept same as a careful and faithful determination of the position of the corner.
- (9-Sec. 4) Established the corner midway and on a straight line between Quarter corner 1317.31' East and Center of Section 1317.31' West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |   |  |
|---|--|
| (2) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nails in:<br>11" R.Maple N18E 15.6' old blazes *<br>12" Oak S83E 8.3' mrkd "1/16S BT"<br>11" Oak S19W 28.6' do<br>10" Oak S65W 43.7' do<br>Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. * denotes 1971 NBT. | (9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:<br>17" R.Pine S23W 36.2' mrkd "1/16S BT"<br>7" Maple clump N56E 33.4' do<br>11" twin Oak S63W 45.4' do<br>6" Maple N22W 39.1' do<br>Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. |
|---|--|



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 9/26/06