

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

| | | |
|------------------------------------|--------------------------------------|---------------|
| Iron | Located In: | Corner Code # |
| <small>(County)</small> | | |
| 1. Public Land Survey | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S <u>2</u> T <u>41N</u> R <u>32W</u> | <u>3</u> |
| | S <u>3</u> T <u>41N</u> R <u>32W</u> | <u>8</u> |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Sep 13 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (3-Sec. 2) North 1/16 corner between Sections 2 and 3. 1978 - Established by A.O.Enger RLS on line between Section corner 19.960 ch. north and 1/4 corner 19.960 ch. south. Set 1"IDx36" iron pipe with 3 3/4" aluminum cap. Red Maple 6 (twin) N40E 46.2', Red Maple 6 N79W 16.5'.
- (8-Sec. 3) West 1/16 corner, Section 3. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (3-Sec. 2) Recovered the 1978 monument in good condition and at record bearing and distance from the remaining 1978 NBT Red Maple N74W in good condition. My measurements show that the monument is located N47W 0.25' from the position intended in 1978 and I accepted same as a careful and faithful determination of the position of the corner.
- (8-Sec. 3) Established the corner midway and on a straight line between Quarter corner 1326.97' west and Center of Section 1326.97' East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|----------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------|
| (3) Fd. 1"ID I.pipe with 3 3/4" alum. MDNR cap. Set measuring nails in: | (8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: |
| 8" Maple N74W 16.9' old blazes * | 18" W.Pine S20E 86.6' mrkd "1/16S BT" |
| 8" Maple S88E 41.3' mrkd "1/16S BT" | 10" Maple clump N02W 66.4' do |
| 10" Oak S50E 66.6' do | 8" twin Maple N20E 47.6' do |
| 8" Oak S85W 22.6' do | 16" R.Pine N70W 72.0' do |
| Fd. sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. * denotes 1978 NBT. | Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. |



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 9/26/06

For the Michigan Department of Natural Resources, Office of Land and Facilities