

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S <u>2</u> T <u>41N</u> R <u>32W</u>	<u>11</u>
	S <u>3</u> T <u>41N</u> R <u>32W</u>	<u>16</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Sep 11 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (11-Sec. 2) Southwest 1/16 corner, Section 2. Not established in the original survey.
- (16-Sec. 3) East 1/16 corner between Sections 3 and 10. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (11-Sec. 2) Established the corner at the intersection of straight lines connecting opposite 1/16 corners. The position for the corner falls within an 11" Oak tree and was not monumented. Placed a WITNESS CORNER 2.00' South of the corner position and on the N-S 1/16 line.
- (16-Sec. 3) Established the corner midway and on the Section line between Quarter corner 1328.90' West and Section corner 1328.90' East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---|
| (11) Set a 1"IDx32" I.pipe with 4" alum. MDNR cap 2.00' South of the corner position and on the N-S 1/16 line for a WITNESS CORNER. Set measuring nails in:
11" Oak N05W 1.65' mrd "1/16S BT"
8" Oak S87E 23.25' do
10" Oak S04W 21.85' do
6" Maple S79W 14.25' do
Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. | (16) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
13" Oak N76E 31.4' mrd "1/16S BT"
8" Sugar S72E 11.3' do
10" Oak S34W 5.1' do
8" Maple N67W 21.2' do
Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. |
|--|---|



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 9/26/06

For the Michigan Department of Natural Resources, Office of Land and Facilities