

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(IRON COUNTY)

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>41</u> N. <u>X</u> , R. <u>32</u> E. <u>X</u> W.	<u>G-3 & H-3</u>
2. PROPERTY CONTROLLING IN SECTION	, T. _____ N. _____ E. _____ S., R. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION	, T. _____ N. _____ E. _____ S., R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April 26, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner G3 (Section Corner 3, 4, 9, & 10, T41N, R32W):
 Wood post (Not found. No subsequent monuments found.)
 Y. Birch 12 S49W 11 (Not found. No subsequent accessories found.)
 Maple 12 N21E 22 (Not found. No subsequent accessories found.)

Corner H3 (1/4 corner between Sections 3 & 10, T41N, R32W):
 Sugar post (Not found. No subsequent monuments found.)
 W. Pine 10 N40W 34 (Not found. No subsequent accessories found.)
 Y. Pine 20 S41E 33 (Probably found. No subsequent accessories found.)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner G3: Restored by double proportionate measurement between 1/4 corner 40.018 ch. W and 1/4 cor. 40.338 ch. E and between original line tree stump 71.759 ch. N and original line tree stump 31.645 ch. S.

Corner H3: Restored from burned stump of original Y. Pine BT, determined as probably being so from its relationship to other line tree stumps and corners to E and W as indicated in original field notes. Stump has no marks but agrees in species and size with recorded original. Corner falls 2.32¹ ch. W of top and south end of hill SW as in original notes.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner G3: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Red Oak 11 N13°W (mag.) 24.0 ft. "S4, NBT"
 Red Oak 6 N41°E (mag.) 22.6 ft. "S3, NBT"
 Red Oak 10 S 8°W (mag.) 16.5 ft. "S9, NBT"
 Declination 0°15' East.

Corner H3: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Red Maple 5 N50°E (mag.) 16.4 ft. "1/4S, NBT"
 Red Maple 5 S17°W (mag.) 16.7 ft. "1/4S, NBT"
 Declination is 0°10' West.


SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE January 19, 1979
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
Arthur O. Enger



Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581