

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(IRON COUNTY)

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. 41 N. S. , R. 32 E. W.	I-2
2. PROPERTY CONTROLLING IN SECTION 3_____	T. 41 N. S. , R. 32 E. W.	7
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. S. , R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner 12 (1/4 corner between Sections 2 & 3, T41N, R32W):
 Sugar post (Not found. No subsequent monuments found.)
 Y. Birch 22 S17E 72 (Not found. No subsequent accessories found.)
 Y. Birch 14 N22W 40 (Not found. No subsequent accessories found.)

Corner 7 (North 1/16 corner between Sections 2 & 3, T41N, R32W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner 12: Restored 4/28/78 on line between Section Corners 39.920 ch. to N and to S.

Corner 7: Established 5/1/78 on line between Section Corners 19.960 ch. N and 1/4 cor. 19.960 ch. S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner 12: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Red Maple 9 S47°E (mag.) 19.7 ft. "1/4S, NBT"
 Red Oak 9 N47°E (mag.) 16.6 ft. "1/4S, NBT"
 Declination is 0°45' West.

Corner 7: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Red Maple 6 (twin) N40°E (mag.) 46.2 ft. "1/16S, BT"
 Red Maple 6 N79°W (mag.) 16.5 ft. "1/16S, BT"
 Declination is 0°10' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE January 10, 1979

CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

