

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(IRON COUNTY)

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>41</u> ^{N.} / _{S.} , R. <u>32</u> ^{E.} / _{W.}	I-3
2. PROPERTY CONTROLLING IN SECTION <u>3</u>	, T. <u>41</u> ^{N.} / _{S.} , R. <u>32</u> ^{E.} / _{W.}	14
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ ^{N.} / _{S.} , R. _____ ^{E.} / _{W.}	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner 13 (Section Corner 2, 3, 10, & 11, T41N, R32W):
 Wood post (Not found. No subsequent monuments found.)
 W. Pine 28 N51W 16 (Not found. No subsequent accessories found.)
 Sugar 16 S43E 14 (Not found. No subsequent accessories found.)

Corner 14 (South 1/16 corner between Sections 2 & 3, T41N, R32W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner 13: Restored 4/27/78 at a point S51°W 161ks. from a down W. Pine which corresponds in species and size with the W. Pine 28 indicated in the original field notes as bearing N51W. Double proportioning this corner from surrounding corners and line trees puts the corner only 3.1 ft farther east and 0.5 ft. farther south of this point, which indicates a probable notekeeper's or compassman's error in relating this BT to the corner.

Corner 14: Established 5/1/78 on line between Sec. Cor. 19.960 ch. S and 1/4 cor. 19.960 ch. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner 13: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Red Maple 5 N 6°W (mag.) 9.9 ft. "S 3, NBT"
 Basswood 5 S48°E (mag.) 21.1 ft. "S11, NBT"
 W. Pine 4 S39°W (mag.) 15.3 ft. "S10, NBT"
 Declination is 0°50' East

Corner 14: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Red Maple 5 N82°W (mag.) 8.6 ft. "1/16S, BT"
 Red Oak 9 N73°E (mag.) 6.1 ft. "1/16S, BT"
 Declination is 0°30' East.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger
CHIEF OF SURVEY PART
MICHIGAN REGISTERED LAND SURVEYOR

DATE January 10, 1979

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

