

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(IRON COUNTY)

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>41</u> ^{N.} / _{S.} , R. <u>32</u> ^{X.} / _{W.}	E-2
2. PROPERTY CONTROLLING IN SECTION <u>4</u>	, T. <u>41</u> ^{N.} / _{S.} , R. <u>32</u> ^{X.} / _{W.}	10
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ ^{N.} / _{S.} , R. _____ ^{E.} / _{W.}	_____
4. LOT NO. _____	, RECORDED PLAT _____	_____
5. PRIVATE CLAIMS _____	_____	_____

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 17, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E2 (1/4 corner between Sections 4 & 5, T41N, R32W):
 Hemlock post (Not found. No subsequent monuments found.)
 Y. Pine 12 S64E 32 (Not found. No subsequent accessories found.)
 Y. Pine 12 N41W 45 (Not found. No subsequent accessories found.)

Corner 10 (South 1/16 corner between Sections 4 & 5, T41N, R32W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E2: Restored on line between Section Corners 40.124 ch. to N and to S. Note: this section line was originally run from north to south the full record distance of 80.00 ch., hence no accumulated error was applied to it as in full-size townships.

Corner 10: Established on line between Sec. Cor. 20.062 ch. S and 1/4 cor. 20.062 ch. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner E2: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Red Pine 6 N62°E (mag.) 44.3 ft. "1/4S, NBT"
 Red Pine 8 S73°E (mag.) 52.4 ft. "1/4S, NBT"
 Declination 1°15' West

Corner 10: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Red Pine 9 S29°E (mag.) 7.5 ft. "1/16S, BT"
 Red Oak 4 N71°E (mag.) 30.4 ft. "1/16S, BT"
 Declination 1°30' West

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE January 10, 1979

CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

