

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	(IRON COUNTY) LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>41</u> N. <u>X.</u> R. <u>32</u> X. W.	E-3
2. PROPERTY CONTROLLING IN SECTION <u>4</u>	, T. <u>41</u> N. <u>X.</u> R. <u>32</u> X. W.	15
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____ R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 17, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E3 (Section Corner 4, 5, 8, & 9, T41N, R32W):
 Hemlock post (Not found. Found monument as set by G. A. Shadko.)
 Hemlock 14 N65E 32 (Not found. Found accessoires by G.A. Shadko.)
 Y. Birch 10 N36W 17 (Not found. Found accessories by G. A. Shadko.)

Corner 15 (West 1/16 corner between Sections 4 & 9, T41N, R32W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner: Corner E3:

Rewitnessed a 3 1/2" x 42" concrete-filled iron pipe with brass plate as set by G. A. Shadko, R.L.S. No. 1934 on July 14, 1960. Shadko's notes state that his monument replaced a "1" iron pipe 3 ft. of it above ground, together with State Hwy. Dept. witnesses, as reported in their surveys of 3/20/36 and 9/-/38." It is not stated whether the highway dept. found the pipe in place or set it, nor by what authority or evidence it was placed. Shadko's witnesses (to 60d spikes driven in the trees):
 W. Pine 18 S 2°W 94.6 ft.
 *Y. Pine 18 S27°E 86.2 ft.
 Poplar 2 N70°E 17.3 ft.

Corner 15: Established on line between Sec. Cor 20.0095 ch. W and 1/4 cor. 20.0095 ch. E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner E3: Monument as described in B, above, with additional NBT's as follows:
 Red Pine 30 S24°E (mag.) 85.2 ft. (Same tree as * above) "S9, NBT"
 W. Pine 4 N29°E (mag.) 62.0 ft. "S4, NBT"
 Declination 1°40' West

Corner 15: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 W. Pine 7 S73°W (mag.) 37.1 ft. "1/16S, BT"
 R. Pine 7 N40°E (mag.) 82.0 ft. "1/16S, BT"
 Declination 1°00' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE January 10, 1979
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

