

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	(IRON COUNTY) LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>41</u> N. <u>X</u> R. <u>32</u> <u>X</u> W.	F-3
2. PROPERTY CONTROLLING IN SECTION <u>4</u>	, T. <u>41</u> N. <u>X</u> R. <u>32</u> <u>X</u> W.	16
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____ R. _____ E. _____ W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner F3 (1/4 corner between Sections 4 & 9, T41N, R32W):
 Maple post (Not found. No subsequent monuments found.)
 W. Pine 26 S30E 19 (Not found. No subsequent accessories found.)
 W. Pine 18 N51W 27 (Probably found. No subsequent accessories found.)

Corner 16 (East 1/16 corner between Sections 4 & 9, T41N, R32W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner: **Corner F3:**
 Restored on 4/26/78 at record bearing and distance from the remains of a W. Pine stump, surmised to be one of the original BT's since a monument set from it bears S89°36.8'E 40.019 ch. from Sec. Cor. to W and S89°57.1'W 40.018 ch. from double-proportioned sec. cor. to E. The second BT would fall in a road and has been destroyed. An iron pipe was reported on 4/7/77 by the survey crew running random lines in this twp. as being in a position N70°44.75'E 32.26 ft. from corner mentioned herein, but by the time I visited the corner on 4/17/78 it had been removed by someone, and I did not actually see any other monuments at this corner.
Corner 16: Established 5/3/78 on line between 1/4 cor. 20.009 ch. W and Sec. Cor. 20.009 ch. E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner F3: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Red Pine 12 N34°E (mag.) 45.0 ft. "1/4S, NBT"
 Red Pine 12 S69°E (mag.) 150.4 ft. "1/4S, NBT"
 Declination 0°25' West

Corner 16: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Red Maple 5 N52°E (mag.) 23.8 ft. "1/16S, BT"
 Red Oak 6 N33°W (mag.) 23.3 ft. "1/16S, BT"
 Declination 0°10' West

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE January 10, 1979
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

