

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	(IRON COUNTY) LOCATED IN--	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY_____	T. <u>41</u> N. <u>X</u> , R. <u>32</u> <u>X</u> W.	G-2	REGISTER OF DEEDS STAMP AND FILING NUMBER
2. PROPERTY CONTROLLING IN SECTION <u>4</u>	, T. <u>41</u> N. <u>X</u> , R. <u>32</u> <u>X</u> W.	14	
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____ S., R. _____ E. _____ W.		
4. LOT NO. _____, RECORDED PLAT _____			
5. PRIVATE CLAIMS _____			

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner G2 (1/4 corner between Sections 3 & 4, T41N, R32W):
 Y. Birch post (Not found. No subsequent monuments found.)
 Y. Birch 6 N34E 33 (Not found. No subsequent accessories found.)
 W. Pine 18 S14W 40 (Not found. No subsequent accessories found.)

Corner 14 (South 1/16 corner between Sections 3 & 4, T41N, R32W):
 Not set in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner G2: Restored 4/26/78 proportionately on line between Sec. Cor. 39.994 ch. S and probable original line tree stump 31.764 ch. N.

Corner 14: Established 4/27/78 on line between 1/4 cor. 19.997 ch. N and Sec. Cor. 19.997 ch. S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner G2: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Red Oak 10 N48°E (mag.) 9.0 ft. "1/4S, NBT"
 Red Oak 6 N 9°W (mag.) 3.4 ft. "1/4S, NBT"
 Red Oak 8 N64°W (mag.) 16.5 ft. "1/4S, NBT"
 Declination 1°15' East.

Corner 14: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Red Maple 9 N58°W (mag.) 41.6 ft. "1/16S, BT"
 Red Maple 8 N65°E (mag.) 17.1 ft. "1/16S, BT"
 Declination 0°30' East.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE January 10, 1979
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

