

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(IRON COUNTY)

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>41</u> N. <u>X.</u> R. <u>32</u> W. <u>X.</u>	E-4
2. PROPERTY CONTROLLING IN SECTION <u>9</u>	T. <u>41</u> N. <u>X.</u> R. <u>32</u> W. <u>X.</u>	3
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ R. _____ E. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 17, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E4 (1/4 corner between Sections 8 & 9, T41N, R32W):
 Cedar post (Not found. Found 1" iron pipe approx. corner mon.)
 W. Pine 12 N43W 20 (Not found. No subsequent accessories found.)
 Maple 7 S51E 30 (Not found. No subsequent accessories found.)

Corner 3 (North 1/16 corner between Sections 8 & 9, T41N, R32W):
 Not established in original survey, but established approximately sometime after 1960, as evidenced by a 3/4" drill rod found bearing S54°15.5'E 3.00 ft. from corner reported herein.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E4: Restored on line between Sec. Corners 39.928 ch. to N and to S and N7°42.1'E 3.26' from a 1" I.D. iron pipe set since 1960 to represent this corner. It was evidently intended to be midway on line between section corners (it is neither), as it could not have been set from any physical original evidence, since the location was examined by a qualified surveyor in 1960 who reported no such evidence, and I perceived none, either.

Corner 3: Established on line between Sec. Cor 19.964 ch. N and 1/4 cor. 19.964 ch. S. The drill rod was evidently supposed to be midway on line between adjacent corners to N and S, but it is neither.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner E4: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Red Pine 18 S11°E (mag.) 54.9 ft. "1/4S, NBT"
 Red Oak 12 S75°W (mag.) 53.8 ft. "1/4S, NBT"
 Declination 0°00'

Corner 3: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Red Pine 5 N79°E (mag.) 74.6 ft. "1/16S, BT"
 Red Pine 5 S56°E (mag.) 70.3 ft. "1/16S, BT"
 Declination 0°40' West

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE January 10, 1979

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

