

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(IRON COUNTY)

FOR CORNERS OF -:	LOCATED IN -:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>41</u> ^{N.} S. , R. <u>32</u> ^{E.} W.	E-5
2. PROPERTY CONTROLLING IN SECTION <u>9</u>	T. <u>41</u> ^{N.} S. , R. <u>32</u> ^{E.} W.	10
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} S. , R. _____ ^{E.} W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER _____

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E5 (Section Corner 8, 9, 16, & 17, T41N, R32W):
 Spruce post (Not found. Found 1" I.D. x 60" iron pipe driven in ground.)
 Cedar 10 N56E 22 (Not found. No subsequent accessory found.)
 Cedar 16 S51W 32 (Found. MDSH & T reference disk nailed thereto.)

Corner 10 (South 1/16 corner between Sections 8 & 9, T41N, R32W):
 Not established in original survey, but established approximately sometime after 1960, as evidenced by a 1" I.D. iron pipe found bearing N51°14.4'W 2.95 ft. from corner reported herein.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E5: On 5/3/78, replaced the found iron pipe with monument described below. Found cedar stump in proper position to SW, which in 1960 was reported by G.A. Shadko, RLS #1934 as still having marks visible, though none are now.

Corner 10: Established 5/17/78 on line between Sec. Cor. 19.964 ch. S and 1/4 cor. 19.964 ch. N. The found pipe was evidently intended to be midway on line between adjacent corners to N and S, but is neither. Note: This section line was run by G.A. Shadko in 1960 and its bearing as determined by him by Polaris observation is S0°47'04"W. By solar observation, I determined it to be S0°46'41"W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner E5: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 3 ft. high old cedar stump S89°W (mag.) 4.1 ft. "S17, NBT"
 Balm-of-Gilead 11 N49°E (mag.) 9.8 ft. "S9, NBT"
 Balm-of-Gilead 10 S86°E (mag.) 17.0 ft. "S16, NBT"
 Declination 0°15' West

Corner 10: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Aspen 7 N27°W (mag.) 21.0 ft. "1/16S, BT"
 Aspen 5 S40°W (mag.) 29.1 ft. "1/16S, BT"
 Declination 0°25' East

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE January 10, 1979
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

