

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	(IRON COUNTY) LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 41 N. R. 32 <del>XX</del> W.	G-4
2. PROPERTY CONTROLLING IN SECTION _____	10, T. 41 N. R. 32 <del>XX</del> W.	10a
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April 27, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- Corner G4 (1/4 corner between Sections 9 & 10, T41N, R32W):**  
 Sugar post (Not found. No subsequent monuments found.)  
 W. Pine 22 S-E 13 (Not found. No subsequent accessories found.)  
 W. Pine 26 N-W 17 (Not found. No subsequent accessories found.)
- Corner 10a (Meander Corner between Sections 9 & 10, T41N, R32W):**  
 (Monument not indicated). (None found. No subsequent monuments found.)  
 B. Ash 6 N55E 34 (Not found. No subsequent accessories found.)  
 Elm 6 N33W 40 (Not found. No subsequent accessories found.)

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner: Corner G4:**

Restored proportionately on line between original line tree stumps N0°19.4'E 8.363 ch. and S0°19.4'W 14.292 ch. Original field notes do not give numerical quantities of quadrants in which the BT's fell, but give the quadrants and distances; found a pine turnover at about proper distance to SE and a possible stump bottom hole at about proper distance to NW, but otherwise could not identify any original evidence.

**Corner 10a:** Restored on N bank of Brule River at record distance from a line tree stump N, and on average bearing of line between that L.T. and another one N of it and the sec. cor. at 3, 4, 9, & 10. Monument falls about 17 feet N of water's edge, but bank appears to have filled in somewhat since the original survey.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Corner G4:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap  
 Red Maple 7 S32°W (mag.) 10.4 ft. "1/4S, NBT"  
 Red Maple 7 S30°E (mag.) 24.0 ft. "1/4S, NBT"  
 Declination is 0°25' East.

**Corner 10a:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap  
 B. Ash 18 N 6°W (mag.) 31.4 ft. "M.C., NBT"  
 B. Ash 8 N55°E (mag.) 21.6 ft. "M.C., NBT"  
 Declination is 1°00' West.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE January 10, 1979

Arthur O. Enger  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

