

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	(IRON COUNTY) LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>41</u> N. <u>X</u> , R. <u>32</u> <u>X</u> S. W.	H-5
2. PROPERTY CONTROLLING IN SECTION <u>10</u>	T. <u>41</u> N. <u>X</u> , R. <u>32</u> <u>X</u> S. W.	15 & 15a
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____, R. _____ E. _____ S. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 28, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner H5 (1/4 corner between Sections 10 & 15, T41N, R32W):
 Hemlock post (Not found. No subsequent monuments found.)
 Y. Pine 18 N59°W 38 (Found. No subsequent accessories found.)
 Y. Pine 24 S71°E 30 (Found. No subsequent accessories found.)

Corner 15 (West 1/16 corner between Sections 10 & 15, T41N, R32W):
 Not established in original survey nor subsequently, apparently.

Corner 15a (Meander Corner between Sections 10 & 15, T41N, R32W):
 Fir 6 for meander post.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner H5: Restored from stumps of two original BT's, no marks and in poor condition, but agree in species, relative size, distance, and bearing with recorded originals, and are confirmed by stumps of original line trees 7.82 ch. (Record 7.83 ch.) and 31.53 ch. (Record 31.48 ch.) East. Position also agrees with record distance to Brule River both to east and to west.

Corner 15: Established on W'y projection of true section line between 1/4 Cor. 1/4 mile east and Sec. Cor. 3/4 mile east, at the record distance of 20.000 ch. from the 1/4 cor.

Corner 15a: Restored on W'y projection of section line described for Corner 15, at record distance of 28.10 ch. from the 1/4 cor. between 10 & 15. Corner falls on margin of Brule River as probably placed in original survey.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner H5: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 *Y. Pine Stump 18 S75 1/2°E (mag.) 20.2 ft. "1/4S, NBT"
 Y. Pine Stump 6 N17°E (mag.) 28.3 ft. "1/4S, NBT" (*Original BT stump.
 Red Maple 6 S9 1/2°W (mag.) 62.3 ft. "1/4S, NBT" Declination is 0°20' West.)
Corner 15: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Red Maple 4 N15°W (mag.) 11.6 ft. "1/16S, BT" (Declination is 0°30' West.
 W. Birch 6 S26°W (mag.) 27.8 ft. "1/16S, BT" Distances are horizontal.)
Corner 15a: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 B. Ash 6 N59°E (mag.) 38.6 ft. "MC, BT"
 B. Ash 8 N52°W (mag.) 47.4 ft. "MC, BT"
 Declination is 1°15' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE Aug 12 1977
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

